# Town of Mammoth Lakes TSMP Project

### **Noise Worksheets**

Provided by PCR Services Corporation

July 2011

## **Appendix**

Construction Noise Calculations



Construction Phase: Mass Site Grading

#### **Equipment**

	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Dozer	1	82	40%	2345	0
Tractor/Loader/Backhoe	1	80	25%	2345	0
Other Equipment	1	85	50%	2345	0
Water Trucks	1	80	10%	2345	0

Receptor: R7

Results:

Hourly Leq: 51



Construction Phase: Fine Site Grading

#### **Equipment**

Reference N	loise
-------------	-------

	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Graders	1	85	40%	2345	0
Tractor/Loader/Backhoe	1	80	25%	2345	0
Other Equipment	2	85	50%	2345	0
Water Trucks	1	80	10%	2345	0

Receptor: R7

Results:

Hourly Leq: 53



Construction Phase: Fine Site Grading

#### **Equipment**

Reference N	loise
-------------	-------

	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Graders	1	85	40%	2345	0
Tractor/Loader/Backhoe	1	80	25%	2345	0
Other Equipment	2	85	50%	2345	0
Water Trucks	1	80	10%	2345	0

Receptor: R7

Results:

Hourly Leq: 53



Construction Phase: Paving

#### **Equipment**

Reference Noise					
	No. of	Level at 50ft,	Acoustical	Distance to	Estimated Noise
Description	Equip.	Lmax	Usage Factor	Receptor, ft	Shielding, dBA
Paver	1	77	50%	2345	0

Receptor: R7

Results:

Hourly Leq: 41